


ARCHITECTURAL



VIDA ARDROUDI
ardroudi.vida@gmail.com

2014-2024

Statement of Authorship

M.Arch Portfolio

I, VIDA ARDROUDI hereby certify that the work submitted in my portfolio for review is entirely of my own hand, or, where produced in collaboration with others, has been clearly identified as such.

Signed: Vida Ardroudi

A handwritten signature in blue ink, consisting of a large, stylized 'V' and 'A' with a horizontal line extending to the right.

Date: 01.03.2025

TABLE OF CONTENTS



01

Project name:
MANGO Ambassador
Location:
Wien / Austria



02

Project name:
NIKE Refil
Location:
Salzburg / Austria



03

Project name:
Marzdaran I6 Train Station
Location:
Tehran / Iran



04

Project name:
University campus central
administrative building
Location:
Tehran / Iran



05

Project name:
Baghdad athletic city
Location:
Baghdad / Iraq



06

Project name:
AL- TAJYAT 60000 seats
olympic & world cup stadium
Location:
Baghdad / Iraq



07

Project name:
AL- TAJYAT 4 star hotel
Location:
Baghdad / Iraq



08



Project name:
AL- TAJYAT 60000 seats
stadium - new Facade
Location:
Baghdad / Iraq



09

Project name:
Shohada civic center
Location:
Mashhad / Iran

PROJECT SAMPLES



Retail- NIKE Salzburg Refit

Total area : 1012.82 sqm

Net sales area : 746.82 sqm


Net Back of House area : 266.00 sqm



Mc Arthur Glen Outlet- eye bird view

ENTRANCE TICKER TAPES DETAILS (B/C BY NIKE)
2X STACKED SINGLE SIDED LED TICKERS TAPES
(3x1024mmx3072mm PER ROW)
- 120MM BETWEEN EACH ROW
- STARTING HEIGHT 2700MM

±4.100m
SLAB



±0.00m
GROUND LEVEL

Location: Mc Arthur Glen Outlet center, Salzburg, Austria

Client: NIKE


Project designer: grupidea Architects

Project coordinator: Gül koc GmbH

Status: Constrction package preparation



Mc Arthur Glen Outlet NIKE store- Existing Facade



Mc Arthur Glen Outlet NIKE store- Cross section cash desk and window display details



Mc Arthur Glen Outlet NIKE store- New Cashing desk area

MARZDARAN TRAIN STATION I6

Length of the platform: 140 meters

Station construction method: underground – piles and ribs

Station infrastructure: 6500 square meters

The final depth of the station from the ground: 23 meters

Number of escalators installed for opening: 10 devices

Number of elevators installed for opening: 4 devices



Location: Tehran, Iran

Client: Tehran Deputy of Transportation and Traffic

Project designer: SABIR International Co./ Central Office


Project Constructor: SABIR International Co.

Status: Finished the construction, Operation stage


I6 train Station Boarding Platform

I6 train Station Main Entrance Building





▲ I6 train Station Main Entrance Facade



I6 train Station Public Stair Case ▲

▼ I6 train Station Ticket Hall



University Campus Central Administrative Building

Location: Tehran , Iran


Client: Shahid beheshti university of medical & science

Contractor: Boland payeh co.


Services : Inclusive engineering services

Architectural designers: Vida Ardroudi and Somayeh Ahmadzadeh

Status: SD and DD



Current buildings



South-East view

Floor plan





This contemporary administrative building has an exterior made of local brick with vertical glass panels that open it up to the exterior and give it a modern and fresh look.

It seeks to reinforce the organic-inspired concepts of the original buildings that reflect the mission and culture of the region. The design of the building and site, work together to connect occupants not only to their immediate surroundings but also to the client's many locations throughout the university campus. The new 25000 square meters facility for 1000 employees features an open work plan and abundant use of natural light to promote a healthy work environment. Conscience effort was made to use local materials, such as brick, in a unique way to contribute to abstract original concepts.

South-West view






Ticket building

Ticket building floor plan

Elevation North sc. 1:150 Facade



Ticket buildings elevation



A successful green-goal urban project located in a flat land that used to be a vast garbage area in the suburbs of Baghdad.

Main purpose:

- To improve culture, urbanization, environment, function, life style, health and hygiene of the region.
- To satisfy the functional requirements of both Olympic and world cup sports events and the organization of other smaller and larger scale events and concerts.


With the goal of expanding youth activities and interests and also to expand the infrastructure of sport in the republic of Iraq, the decision was made on the establishment of stadium with a capacity of 60,000 spectators in the city of Baghdad including all services according to technical requirements of FIFA. Therefore, the American Hill international Inc. held a tender competition on behalf of client. Boland Payeh construction company attended and competitively enabled to win the tender. The project started on 2011 in Bagdad.

The work includes design and execution of the main stadium, as well as the gates and roads leading to the stadium, three 500 seats training stadium, a 2000 seats stadium, a 4 star hotel and all other works suitable to maintenance this athletic city (turnkey job).

Bagdad athletic city is located in a flat land in suburbs of Bagdad about 516 acres that was used to be a vast garbage area of the city. In order to achieve the goals which stated in main purpose above, a decision was made by the minister to allocate this land to Baghdad athletic city.


I accepted the responsibility of architectural design and cooperated with a group of well experienced Iranian architects and followed the highest international standards like 2012 IBC code and commentary, 5th edition 2011 football stadiums FIFA technical recommendations and requirements to accomplish FIFA ratification. Eventually, my colleagues and I fulfilled all requirements of this project professionally and honored to achieve FIFA approval.

AL-TAJYAT
BAGHDAD
MASTERPLAN



Location: Baghdad; Iraq
 Client: Ministry of Youth and Sports
 EPC Contractor: Boland Payeh Construction
 Engineering Management (BP Co.)
 Client Consultant: Haris Engineering (USA)
 Collaborative Consultants: NCK INC. (Canada)
 WERNER SOBEK GROUP (Germany)
 Status: Under construction
 Senior Architect: : Vida Ardroudi
 Architectural team: Zeinab alizadeh, Somayeh Ahmadzadeh,
 Leila Ketabchi, Saba Raad, Atieh Asadiha, Shideh Pourjoola
 Phases: SD, DD, CD, CA



01. MASTER PLAN AND VEHICLE ACCESS




Evenly distributed precinct entrances have been provided around the stadium with two separated barriers or security check and controls.

The first security check at the outer perimeter fence is for ticket prescutiny, bag and magnetometer checks (Mag & Bag's).


The second will be made at the stadium turnstiles, with sufficient space between the border of the secure stadium precinct and the stadium turnstiles to permit the free movement of spectators.



The structure for Mag and Bag's will be installed on a temporary basis for match days. Sufficient space is available to accommodate spectators waiting to be searched. Mag and Bag's is located between the public parking and the entrances to the main pedestrian ring road. This will allow for queuing along the pedestrian boulevards.



A sufficient number of turnstiles have been provided at each entrance staircases. The required minimum is 1 per 700 spectators. Therefore 86 turnstiles were provided to accommodate 60000 spectators. Turnstiles positioned on the landing on the top of the main access ramps prior to entering the stadium concourse. This will allow for the spectators to move freely along the pedestrian ring road once they have passed through the first security barrier.



The access to the eastern stair is unique to the rest of the main stadium staircases. In order to access the eastern stairs, epectators currently cross or walk along the logistics entrance road. Alternatively, sufficient pedestrian access and crossing points provided along this road.

AL-TAJYAT 60000 seats Olympic and World cup Stadium



Location: Baghdad; Iraq
 Client: Ministry of Youth and Sports
 EPC Contractor: Boland Payeh Construction Engineering Management (BP Co.)
 Client Consultant: Haris Engineering (USA)
 Collaborative Consultants: NCK INC. (Canada) - WERNER SOBEK GROUP (Germany)

Status: Under construction
 Senior Architect: : Vida Ardroudi
 Architectural team: Zeinab alizadeh, Somayeh Ahmadzadeh, Leila Ketabchi, Saba Raad, Atieh Asadiha, Shideh Pourjoola
 Facade Basic Design: WERNER SOBEK GROUP (Germany)
 Facade Detail Design: Vida Ardroudi, Shideh Pourjoola
 Phases: SD, DD, CD, CA

The new AL-TAJYAT stadium with the area of 74500 m² offers a capacity for 60000 spectators. The stadium is situated in the center of the site like a gem on a ring. It forms the new landmark of AL-TAJYAT region in BAGHDAD city and adds an imposing and monumental shape to the northern cityscape of Bagdad. General formation of the stadium reflects the cultural field and architectural heritage of Bagdad with modernity.


It also emphasizes on the distinguished contemporary architectural philosophy of sport stadiums.

Beside the large Arena, three 500 seats training stadiums, a 2000 seats stadium as a visual and spatial continuum and a 4 star hotel are laid out in the site which reflect the architectural language of the stadium and appear as an ensemble without undermining the unquestioned dominance of the stadium.




AL-TAJYAT 60000 seats Olympic and World cup Stadium

06



- LOGISTICS
- MEDICAL
- SECURITY
- COMMERCIAL
- CONCESSIONS
- SPECTATORS
- IT & T
- MEDIA
- CEREMONIES
- FIFA/LOC OFFICE
- COMPETITIONS
- VVIP PROTOCOL
- TICKETING

Event level plan ▲



Main concourse level plan ▼


- LOGISTICS
- MEDICAL
- SECURITY
- COMMERCIAL
- CONCESSIONS
- SPECTATORS
- IT & T
- MEDIA
- CEREMONIES
- FIFA/LOC OFFICE
- COMPETITIONS
- VVIP PROTOCOL
- TICKETING

AL-TAJYAT 60000 seats Olympic and World cup Stadium

I was chosen as the senior architect of Baghdad Athletic city project, when basic architectural design had been approximately finished and detail design was about to start developing. But BP Company as the EPC contractor was due to suspend the construction by reason of huge costs which did not correspond to fixed amount of the turn key contract.


I came to investigate all relative documents and realized that the architectural drawings were suffering the unnecessary over designs and consequently so were MEP and structural drawings.

Although almost 30 percent of the structure had been constructed previously, I revised almost all architectural basic drawings and redesigned 3 levels of the stadium (event level, main concourse level and upper concourse level) completely based on technical FIFA requirements and eventually succeeded to eliminate about 34500 square meters of architectural over designs and decrease about 23 percent of the costs as bellow:




EVENT LEVEL- Previous situation

Grid H (highlighted ring) with area about 7800 square meters removed.




EVENT LEVEL- Current situation

By rearranging and redesigning Event level plan completely based on FIFA requirements, highlighted part with area about 8900 square meters was freed and made available for future development




MAIN CONCOURSE LEVEL- Previous situation

Grid H (highlighted ring) with area about 8900 square meters removed.




MAIN CONCOURSE LEVEL- Current situation

Spectator's 16 stair cases was moved from ring H and relocated within radial grids.




UPPER CONCOURSE LEVEL- Previous situation

Grid H (highlighted ring) with area about 8900 square meters removed.




UPPER CONCOURSE LEVEL- Current situation

Spectator's 16 stair cases was moved from ring H and relocated within radial grids.



CROSS SECTION- Previous situation

Grid H (highlighted ring) was removed and the Facade relocated at Grid G



CROSS SECTION- Current situation

Stadium's roof was moved about 4 meters lower.



AL-TAJYAT 60000 seats Olympic and World cup Stadium



Large Arena has 5 levels with specialized functions; Event floor level, main concourse and upper concourse level, VIP/VVIP level with a separated hospitality area and the last floor, media level. Each level has been designed based on FIFA diagrams and completely complies with FIFA requirements. The stadium bowl and stand structure is designed as an elliptical, open framework from precast concrete components.

The new roof structure sets itself apart from stadium typology with its simple construction and choice of surface material.





The steel roof is designed as a light cantilevering radial truss structure and outfitted corrugated metal and translucent polycarbonate sheets. The roof rests on 152 concrete columns.





The spectacular 54m high Façade with 800m perimeter is the largest Façade in Iraq and raises high around the stadium as a landmark visible from afar. It unfolds itself with its white cladding like a radiant flourishing bloom in desert. The stadium's shell was designed as an abstract chained-link arches, which transforms the stadium into a sculpture and intensifies its integration with the indigenous, religious and cultural architecture of Iraq.

The complex and iconic Façade with the perforated metal sheeting allow views from plazas to all sides of the site and its transparent and open character invites to passive and active participation. Additionally, It provides protection against driving rain, strong winds and direct sunlight without excluding the outside world.



AL-TAJYAT 60000 seats Olympic and World cup Stadium

Interior design / Designed by: Vida Ardroudi




▲ Main Entrance / Event Level

◀ VIP Lobby / VIP Level

▼ VIP & VVIP Lounge / VIP Level





The 4 star hotel is located in the Baghdad athletic city and has been considered to be used for players , coaches and referees during competition time. The total area is about 5500 sqm with 3 storeys. The concept design of the hotel is centered around simplicity; a modern hotel with traditional feeling.

It aims to put vernacular ornaments of Baghdad's traditional houses at the heart of the hotel's Facade. While organizing the hotel layout into 74 rooms and suites, restaurants and bars, the underlying aim of the architect was always to create a veritable window to the outdoors and the site. In common with other projects, my colleagues and I set aside plenty of time for research in order to understand and immerse ourselves in the site. Such "contextual immersion" allowed us to develop a contemporary approach that is in symbiosis with the country's traditional culture.

We wanted to adopt a local style and retain the influence of Iraqi architecture on both the interior and exterior of the hotel, albeit in a modern and up-to-date way.



Location: Baghdad; Iraq
 Client: Ministry of Youth and Sports
 EPC Contractor: Boland Payeh Construction Engineering Management (BP Co.)
 Client Consultant: Haris Engineering (USA)
 Collaborative Consultants: NCK INC. (Canada)
 WERNER SOBEK GROUP (Germany)
 Status: Under construction
 Senior Architect : Vida Ardroudi
 Architectural team: Zeinab alizadeh, Atieh Asadiha, Shideh Pourjoola
 Phases: DD, CD, CA



New Alternative Facade / Designed by: Vida Ardroudi



By client's request to reduce costs of the project, I started to think about the stadium's Facade.

Despite the very professional and magnificent design of the previous Façade, It has three weaknesses :

- 1- Costly and not compatible with fixed price contract of the turnkey project .
- 2- Heavy structure
- 3- Complications of installation.

I do believe that a good design should be more simple while being spectacular and unique without weaknesses of the previous Facade . New Façade has following advantages:


1. It has been formed by just one module that mirrors in each axes.

2.It has been confined in one spam. So, this causes a more simple structure than before. Each arch In previous façade design, is limited between 3 and 5 spams. So, structural frames of each arch should rotate around the stadium in each grid and causes a complicate and heavy structure.

3.I preferred to utilize structural frames to complete the architectural design. So, the new design is a combination of structural and architectural elements. For instance, I chose I shaped frames around architectural elements. Therefore, the new Façade does not need any cladding to hide structural elements. (Total area of previous facade cladding is about 50000 m².)

4.It still has an Iraqi, domestic and distinctive architectural shape. I was inspired by traditional geometrical and architectural ornaments of Baghdad's grand Bazaar that mostly have been applied under the domes.


Muqarnas dome, tomb of Sitt Zubaida in Baghdad





BAGHDAD's heritage; reliable source of inspiration :

- Myths
- People, Culture, Life style
- Handy crafts
- Architecture




Pu'abi or Shab'ad
"The Sumerian princess"




Iraqi carpet
use of geometrical patterns



Abbasid palace Gate in
Baghdad



an arch in the Abbasid
al-Mustansiriyya school in Baghdad




AL-TAJYAT 60000 Seats Stadium - New Facade








Lozenge shaped architectural ornaments have made a unique diamond pattern under the dome ceiling of Baghdad's grand Bazaar. These patterns inspired me to design the stadium's new Facade.

I chose tensile membrane material to cover the elements. It has three advantages:


- a- Light weight material.
- b- Bringing variable and professional lighting designs for night view.
- c- Reasonable costs rather than cladding and infill shroud material.



AL-SARAY grand Bazaar in old part of Baghdad in Iraq



New Alternative Facade / Designed by: Vida Ardroudi




In traditional Persian architecture, town squares are known as “maydan” or “meydan”. A maydan is considered as one of the essential features in urban planning and they are often adjacent to bazaars, large mosques and other public buildings. Shohada square, as a focal point in Mashhad, is one of the main arteries of access to Holy shrine of Imam Reza and grand Bazaar and makes access to utilities and major axes.

At the beginning of its formation, in the early AD century present, Shohada square was a symbol of a non-traditional urban spaces that six new urban arteries intersected. Symbols of modernity, such as municipal building, fire and electric office building on the square, took Mashhad as a hub for new developments.

After 2000, the square became the focus of attention, as a large commercial center of the city and a civic center for 14 million pilgrims a year. The site was considered a strong prospect for new building and became the subject of much debate among architects and planners. The square was also viewed as a place where the city of Mashhad could reestablish its position in modern Iran. More than just building a site, Shohada square became a reference of post revolution architecture and urban design attitudes.

The generalities of the grand Shohada Square Project were approved by Mashhad Municipality in Dec.2003. The project was defined in an area of 23 hectares with the aim of converting this significant city area to an urban space.

The new plan consists of two tunnels (one from west to east and the other east to west) for reducing the heavy traffic on the main level of the project. An extension to the old municipality building and a new city hall are planned, along with more than four other official and commercial buildings. Two hotels, a new boulevard, shopping malls, and a large plaza are also planned.



Location: Mashhad , Iran
 Client: Mashhad municipality
 Consultant: TAJEER architects and urbanists
 Services : Inclusive engineering services
 Architectural designers: Nadereh Nazary, Amir Abbas Shirazi, Hengameh Hoseini, Elham Amini, Vida Ardroudi
 Status: Under construction
 Phases: SD, DD, CD, CA



SHOHADA civic center and square, Mashhad, Iran, 2015



SHOHADA square , Mashhad, Iran, 1954

SHOHADA square , Mashhad, Iran, 2002





Main purpose:

- Organizing traffic in a great part of the city leading to the Grand Bazaar.
- Restructuring the square and the neighboring area with the aim of providing a desirable urban environment.
- Creating a green area and a square for safe passage of pedestrians and vehicles.
- Creating an ideal urban image which is nostalgic and has an urban identity.





Project features:


- Area 135,000 sqm
- Adjacent to Mashhad grand Bazaar.
- Adjacent to traditional municipality building.
- Inspired from formative motif of Iranian architecture and geometry.
- Make use of abundant symbolic geometry, using pure forms such as circles and squares, and plans are based on often symmetrical layouts featuring rectangular courtyards and halls.





THANK YOU



ARCHITECTURAL



VIDA ARDROUDI
ardroudi.vida@gmail.com



Phone: 015906117071